

IRRIGATION TECHNICAL SPECIFICATIONS

EFFECTIVE JUNE 1, 2026



**EAST CHERRY CREEK VALLEY
WATER AND SANITATION DISTRICT**
6201 South Gun Club Road
Aurora, Colorado 80016
Phone: 303-693-3800

THIS PAGE INTENTIONALLY LEFT BLANK

**EAST CHERRY CREEK VALLEY WATER AND SANITATION DISTRICT
IRRIGATION TECHNICAL SPECIFICATIONS**

TABLE OF CONTENTS

SECTION 1.	GENERAL.....	1
1.01	PURPOSE	1
1.02	DISTRICT SERVICE AREA	1
1.03	AUTHORITY	1
1.04	REVISIONS	1
1.05	DESIGNER QUALIFICATIONS	1
1.06	VARIANCE	2
1.07	DEFINITIONS	2
1.08	ABBREVIATIONS	4
SECTION 2.	IRRIGATION SYSTEM DESIGN.....	5
2.01	GENERAL	5
2.02	IRRIGATION DESIGN PLAN	5
2.04	SOIL PREPARATION REQUIREMENT	6
2.05	PLANT TYPES AND DEFINITIONS	6
2.06	IRRIGATION SYSTEM REQUIREMENTS	7
2.07	PERFORMANCE STANDARDS FOR WATER USES	12
2.08	TAP SIZING FOR LANDSCAPE IRRIGATION	13
2.09	IRRIGATION SCHEDULE	13
2.10	TAP FEES	14
2.11	PRE-CONSTRUCTION MEETING	14
2.12	CONSTRUCTION OBSERVATION	15
2.13	FINAL INSPECTION	15
2.14	SYSTEM EFFICIENCY TEST	16
2.15	SYSTEM MAINTENANCE, CONTROLLER SCHEDULING, AND SYSTEM AUDITING	16

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 1. GENERAL

1.01 PURPOSE

This publication provides information relative to engineering, design, material specifications, and construction procedures for irrigation systems within the East Cherry Creek Valley Water & Sanitation District (District). All irrigation system designs shall be submitted for review and approval prior to the issuance of an irrigation tap for non-single family residential properties. Any deviation from these requirements must be approved by the District in writing. Irrigation systems will be inspected during and after installation to assure compliance with these requirements and that the system was installed as it was designed and approved.

These design and usage requirements are put forth to encourage and promote the conservation and efficient use of water. Higher water usage and maintenance expenses may be reduced or limited when these irrigation system requirements are followed during the design, installation, and ongoing maintenance. These required irrigation efficiency measures shall apply to all new irrigation systems, except single family residences.

These Specifications are an integral part of the District's Rules and Regulations. The Specifications may be downloaded from the District's website at www.eccv.org/technical-specifications. District's Specifications may also be purchased at the East Cherry Creek Valley Water & Sanitation District Office, located at 6201 South Gun Club Road, Aurora, Colorado 80016, at cost.

1.02 DISTRICT SERVICE AREA

The East Cherry Creek Valley Water and Sanitation District Service Area is located in Arapahoe County, Colorado. Generally, the District is located west of Gun Club Road, south of Hampden Avenue, east of Parker Road, and north of Arapahoe Road.

1.03 AUTHORITY

These Specifications shall be administered by the District and shall include all interpretation, enforcement, revision, waiver and variance with all such actions being finally determined by the District.

1.04 REVISIONS

These Specifications are effective as of June 1, 2026. Revisions to these specifications may be made from time to time by the District. Any revisions shall be in effect at the date of issuance by the District. Any person using these specifications should contact the District for information relative to revisions.

1.05 DESIGNER QUALIFICATIONS

The irrigation designer shall be a certified irrigation designer (commercial) as regulated by the Irrigation Association, or other professional with extensive

experience in the design of commercial irrigation systems as determined by the District Manager. The designer shall upon request, produce evidence of their experience that may include references, letters of recommendation, portfolio of work, photographs, and employment records.

1.06 VARIANCE

The applicant may request a variance from these requirements from ECCV. Any such variance request should be made to ECCV in writing and any approved variance request or response from ECCV should also be made in writing. These are the current ECCV Irrigation System and Water Conservation Requirements, but these requirements are subject to revision and update by ECCV at any time.

1.07 DEFINITIONS

As used in these Specifications and the District Rules and Regulations, unless the context clearly indicates otherwise, the words defined below shall have the respective meaning set forth for them:

Actual Costs: All direct and indirect costs attributable to any project or material, equipment, administrative, and overhead expenses, calculated in accordance with the rates set forth in the District Rules and Regulations, and all direct payments to third parties, at cost.

Board or Board of Directors: The duly constituted Board of Directors of the District.

Contractor: Any person who performs any work, either for himself or another, on any water facilities, public or private, within the District, including all subcontractors, agents, employees, officers, and other representatives of such person.

Construction Plans: Plans and Specifications for the construction of a specific Developer/Owner water system project which have been reviewed and signed by the District and the District's Consulting Engineer.

District: East Cherry Creek Valley Water & Sanitation District, Arapahoe County, Colorado, its employees, agents, officers, directors, insurers, and professional consultants.

District Engineer: The District's Staff Engineer and/or the District's Consulting Engineer.

District Manager: The Manager of the District appointed by the Board of Directors, or any other person duly authorized to perform the duties of District Manager.

District System: The Plant, facilities, systems, assets, and appurtenant property rights owned or directly controlled by the District.

Foreign Material: Any objects or substances other than treated potable water.

License: The written authority to receive water at specified premises for specified purposes.

Licensed Premises: The land area and improvements thereto to which water service is limited under any particular License.

Main or Water Main: Those pipes and appurtenant facilities used for distributing water along public streets or appropriate rights of way deeded or licensed to the District directly to various Licensed Premises.

Main Extension: The construction of any facilities, or the facilities themselves, which are intended to become a part of the District System upon acceptance by the District in accordance with the Rules and Regulations.

Person: Associations, corporations, firms, partnerships, and bodies politic and corporate, as well as individuals.

Property Owner/Owner/Developer: All of these terms shall be synonymous with each other and shall mean any person who, whether solely or with others, owns real property within the District. When property is owned by more than one person, the term includes all owners thereof. As used in these Specifications, the term shall apply to such person only in connection with his ownership of any specific parcel of real property involved in any specific matter governed by these Specifications or the Rules and Regulations. For purposes of clarity, the masculine singular pronoun is used in these Specifications to refer to Property Owner.

Record Drawings: A separate set of construction plans marked to indicate completely and accurately the field-installed condition of facility construction in progress, as required by these Specifications.

Rules and Regulations: The comprehensive set of operating rules and requirements, as now or hereafter constituted, adopted by the Board of Directors for the purpose of regulating the design, construction, operation, maintenance, use, repair and replacement of the District System.

Service Lines: All pipes, fittings, and appurtenances which convey water from the District System to the plumbing of the Licensed Premises. In the case of an inside water meter, the dividing point between the District System and private service line is the plug on the corporation stop tapped into the Main. In the case of an outside water meter, the dividing point is at the water meter

Stub-in: A tap made for the purpose of installing service lines prior to the paving of streets. Such connection shall include fittings necessary to extend the service line to the valve at the property line.

Tap or Service Connection: The physical connection to a District Main which, together with the Tap Permit for same, affects water service to any Permitted Premises.

1.08 ABBREVIATIONS

These Specifications utilize and otherwise make reference to other Technical Specifications. Where these references are made, they shall refer to the latest edition or revision thereof.

AASHTO	American Association of State Highway and Transportation Officials
ACI	American Concrete Institute
AISC	American Institute of Steel Construction, Inc.
ANSI	American National Standards Institute, Inc.
ASA	American Standards Association
ASTM	American Society of Testing Materials
AWWA	American Water Works Association
DU	Distribution Uniformity
ET	Evapotranspiration
FPS	Feet Per Second
FT	Feet
GPM	Gallons Per Minute
IPC	International Plumbing Code
PSI	Pounds Per Square Inch
SEMSWA	Southeast Metro Stormwater Authority
SQ	Square
OSHA	Occupational Safety Health Administration
UL	Underwriter's Laboratories
UNI	Uni-Bell Association
UPC	Uniform Plumbing Code
YR	Year

SECTION 2. IRRIGATION SYSTEM DESIGN

2.01 GENERAL

All water lines, appurtenances, and related public water system within the District shall be designed in accordance with these Specifications, and any other applicable Federal, State, and Local regulations. Any deviation from these Specifications shall require the written authorization of the District prior to design or construction. The intent is to provide a consistently designed, long-term, reliable system which can be easily located and maintained by the District.

2.02 IRRIGATION DESIGN PLAN

An irrigation design plan and project cover letter shall be submitted and approved by the District Manager prior to installation of any non-residential irrigation system. The project cover letter should provide a brief project overview and description of the landscaping and include system details including any unique water use aspects, features, or requirements.

The irrigation design plan shall accurately and clearly identify:

- A. Property boundaries
- B. Locations, model and size of all components of the irrigation system
- C. Static water pressure and elevation at the point of connection
- D. Flow rate, zone number, application rate (inches per hour), and design operating pressure for each zone or station on the controller
- E. Backflow Preventer
- F. The total square footage of the following material types.
 - 1. Irrigated turf grass
 - 2. Low water use turf grass
 - 3. Native and non-irrigated grass
 - 4. Traditional shrubs and perennials
 - 5. Xeriscape or xeric shrubs and perennials
 - 6. Annual flower and color beds
 - 7. Tree only areas
- G. Describe the use of subsurface or drip irrigation on the project, if applicable.
- H. Site water requirements
- I. A pressure loss worksheet

- J. Calculation of the total expected water usage in gallons per year with a breakdown of the usage by category of each type of irrigated plant material.

2.03 LANDSCAPE DESIGN AND PLANT SELECTION

The District understands and values the contribution of high quality landscaping to the look and feel of our neighborhoods and community. At the same time, the District encourages the thoughtful design and the strategic use of plant materials that reflect our natural, semi-arid environment and that require lower water use where possible while providing the necessary quality of aesthetics and long term sustainability for a given site and location.

2.04 SOIL PREPARATION REQUIREMENT

The soil in all irrigated landscape planting areas: turf, shrub beds, and native grass areas should receive proper soil preparation to improve the soil condition and water holding capacity of the rootzone. For irrigated areas, 5 yards of organic soil amendment per 1000 sq.ft. should be incorporated or tilled in to a depth of 6" or deeper.

Areas that are to be planted in a native grass should also receive a similar soil preparation, but at a lesser, 2 yards per 1000 sq.ft. The District is not specifying the type of soil amendment at this time, but expect that typical, quality soil amendment products will be used. The District may request soil amendment delivery tickets and inspect soil preparation to verify compliance.

2.05 PLANT TYPES AND DEFINITIONS

The following descriptions are provided to clarify and allow for categorization of the typical landscape planting areas and their water use requirements. Plant materials with similar water demand requirements shall be grouped together for effective and efficient irrigation.

A. Irrigated Turf Grass

All traditional, high quality, high use lawn areas that are managed for foot traffic, athletics, or aesthetics and that are actively maintained or mowed on a weekly basis during the growing season. Irrigated turf has a high water use requirement. Examples of high water use turf grass include (but not limited to): Kentucky Bluegrass, Ryegrass, and Tall Fescue.

B. Low Water Use Turf Grass

These are secondary and more peripheral grass areas that are managed and maintained to a lower usage and/or lower aesthetic standard. They require less water, are mowed infrequently usually less than once a month. This turf is irrigated to keep the areas healthy and green, but require and will use 25-50% less water than irrigated turf grass. Examples of low water use turf grass include (but not limited to): Blue Gramma, Buffalograss, and Bermudagrass.

C. Native and Non-Irrigated Grass

This grass or area may be irrigated initially for establishment, but otherwise is not intended to be irrigated on an ongoing basis. It is intended to be generally a thinner and less green look that is suitable for natural areas that do not receive a lot of use or require a lush, green aesthetic. This grass is intended to grow and survive on natural precipitation.

D. Non Turf Area: Traditional Shrubs and Perennials

These plantings are primary, high visibility areas with plant materials that require regular and consistent watering to maintain their health and aesthetics. These areas should be mulched with wood or rock products to aid in water retention and to minimize erosion and runoff.

E. Non Turf Area: Xeriscape or Xeric Shrubs and Perennials

These are specially selected low water use, often native plant materials that typically need some, but not a lot of supplemental irrigation to maintain their health and aesthetics. These can be used in primary areas, but are especially useful to conserve water on a site when used in secondary or more peripheral shrub areas.

F. Non Turf Area: Annual Flowers and Color Beds

These have high water requirements and are best used only in high visibility, high use areas that are within close proximity to people. Annuals have their place and provide great aesthetic value, but should be strategically planned and carefully irrigated.

G. Tree Only Area

Tree only areas are defined as trees that require irrigation and that are located in Native Non-Irrigated Grass areas. These have water requirements similar to Irrigated Turf Grass areas based on the mature canopy size.

2.06 IRRIGATION SYSTEM REQUIREMENTS

A. Flow Requirements

The system shall be designed so it is capable of providing sufficient water for adequate plant growth during periods of peak demand when Evapo-Transpiration (ET) is highest. Peak demand shall be based on 1.8 inches per week for turf and 1.0 inch per week for planting beds. Water requirements for each site must be determined prior to designing the system in order to size the system for adequate capacity.

B. Site Water Budget

The system should be designed for a total water budget of 1.5 inches per week in the combined turf and planting beds.

C. Run Times

All irrigation systems shall be designed and managed to operate no more than the durations outlined on the ECCV website below:

<https://www.eccv.org/watering-schedules>

Due to ongoing drought conditions in Colorado, irrigation systems must be monitored and adjusted frequently to ensure compliance and efficient water use. These requirements are subject to change at any time as determined by the District. Water restrictions may also be implemented at any time, which could further limit run times, water usage, and allowable watering days or hours.

Subsurface drip irrigation may be permitted to operate outside the standard watering window with prior approval from the District.

D. Controller

The proposed controller type and any required weather stations, rain sensors, subscriptions, or related components shall be submitted to the District for review and approval.

All automatic controllers shall have the ability to make automated scheduling adjustments based on site conditions and localized weather events. The controllers shall have onsite weather sensors or web-based communications to receive or calculate daily ET and make daily watering adjustments. All controllers shall include a local rain sensor or tipping bucket to automatically shut the system down for a prescribed time during a rainfall event. Soil moisture sensing controllers and equipment are allowed and may also be used.

The design shall include provisions for any initial subscriptions required to operate the ET-Based controllers for the first two seasons. It is the responsibility of the Owner to continue the subscriptions as general maintenance of the system.

If a non-ET or non-weather based controller is planned, a proposed mid-season irrigation schedule is required.

The controller shall be capable of providing the required water based on the District's weekly watering schedule.

E. Pressure Control

In order to control pressure and protect the system from damage, pressure reducing valves shall be installed immediately downstream of the backflow preventer if static pressure is in excess of 100 psi. Pressure regulation at the zones remote control valve is recommended if pressure is 15 psi above the system design pressure. System design pressure is the required operating pressure at the head plus system pressure losses including meter and service line losses.

Pressure at all heads should be within 10 percent of the system design operating pressure.

Example: A head designed for 30.0 PSI should operate within the 27.0 to 33.0 PSI range. This should be consistent if the pressure regulating heads are utilized. These are typically only available in the spray body type sprinklers. This shall be accomplished by using pressure reducing, or regulating, valves (not flow control valves or flow restriction devices) installed under or in the base/stem of the head. A combination pressure reducing and control valve can be used to control the pressure within a zone.

Booster Pumps are not permitted unless pre-approved by the District. Booster pumps must be equipped with an automatic pressure shut off device.

F. Sprinkler Head Layout

Head spacing shall not exceed 50 percent of the diameter of its effective coverage in permanently irrigated, what is commonly referred to as head to head coverage. The system shall be designed to avoid overspray onto buildings, asphalt, concrete, including walkways.

Head placement and selection shall be designed to provide matched precipitation rates and efficient Distribution Uniformity (DU).

1. Slopes in excess of a 3 to 1 ratio

Heads placed at the bottom of a slope need to be valved separately. Mid-point on the slope will need a moderate amount of water and therefore these heads shall also have their own zone. Heads placed on the top of the slope must be valved separately, as they will water for the longest period of time. Lateral lines on slopes shall be installed along the contour rather than up and down the slopes.

2. Narrow strips and medians

If the area is less than 15 feet wide, use pop-up spray heads with a nozzle radius that does not exceed the width of the strip. If the area is less than four feet wide, eliminate turf in favor of tree and shrub plantings if possible, or install subsurface drip irrigation.

G. Zoning For Control

Irrigated areas shall be divided into Hydro-Zones that have the same water requirements such as turf, planting beds, ground cover, etc. Cultivated planting beds will require more water than areas that are mulched with wood, rock, or other products.

Identify any low areas, drainage ways, and storm water detention ponds, and zone these low or bottom areas separately from the adjacent areas. Heads and valves shall be installed adjacent to and outside of these low areas where possible.

All heads within a given zone must have matched precipitation rates, i.e., bubblers, rotors, spray heads, and must be zoned separately. Parking lot medians and islands, due to the surrounding asphalt and heat, will require more water and thus should be on a separate zone.

H. Hydraulics

The submitted irrigation design should include a pressure loss worksheet for the zones with the highest flow and furthestmost from the source, listing the following:

1. Valve number and flow rate
2. Available static water pressure at source
3. Loss or gain due to elevation
4. Detailed list of various component pressure losses and velocities
5. The operating pressure requirements
6. Project location and date
7. Water service & expected meter size

Table 2.01: Average Flow & Pressure Losses of Displacement Type Meters and "K" Copper Pipe

Maximum Capacity AWWA Flow Criteria			70% of Max		"K" Copper (C=130) Service Line Loss	
Size	GPM	PSI Loss	GPM	PSI Loss	PSI/100 ft	PSI/50 ft
1"	50	9.3	35	5.5	41.2	20.6
1-1/2"	100	11.3	70	7.5	21.5	10.7
2"	160	10.4	112	5.7	13.2	6.6
3"	300	13.1	210	7.3	6.1	3.1
4" and Larger	Contact District for sizing criteria					

Use 70 % of the maximum safe water flow for all irrigation systems.

I. Backflow Preventer & Specialty Valves

Back Flow devices shall be reduced pressure principle type and shall be installed per manufacturer recommendations. Maximum velocity for water flow through backflow preventers shall not exceed 7.5 fps. When

using pressure-reducing valves, the sizing shall be based on the valve's flow capacity at a reduced pressure level.

Backflow Preventers shall be in locked and secure enclosures, typically secured to a concrete pad, or in a locked, indoor room to prevent unauthorized access and theft. Enclosures should be kept locked at all times.

J. Pipe Sizing

Pipe sizing shall be calculated to ensure flow velocities do not exceed 7.5 fps in copper service lines and mainlines, and 5 fps in plastic mainline and lateral piping.

K. Pressure Difference

The pressure difference between any two heads in the zone shall not exceed 10 percent of the highest pressure within the zone.

L. Equipment Selection

New, quality, commercial grade equipment shall be used for all system components.

M. Drip Systems

Continuously self-flushing, pressure-compensating drip irrigation or subsurface tubing is encouraged in non-cultivated planting beds that are mulched or in narrow turf strips where spray heads are not practical. Drip irrigation zones should be properly zoned for varying plant water requirements, slopes, and exposures. Drip control valves assemblies shall include a filter and pressure regulator.

N. Spray Heads

Pop-up spray heads shall have a pressure regulating device set at the pressure for optimal performance as recommended by the nozzle manufacturer. The regulator shall be integrated in the base of the stem. A manufacturer installed check valve shall be included to reduce low head drainage.

Heads shall seal in the operating position at 10 psi or less, and the water used in the flush mode shall not exceed 0.05 gpm. Head shall have a ratcheting feature for adjusting the direction of spray.

1. Pop-up spray heads for turf areas shall have a minimum pop-up height of 6-inches.
2. 12-inch pop-up height heads will be used in shrubs, ground cover, and flower beds, but drip irrigation shall be used when possible

High efficiency stream or spray nozzles are required on all heads to improve the distribution uniformity and overall efficiency.

O. Rotary Heads

Use an internal drive, closed case rotor with wiper seals and spring retraction. Pop-up stem surface diameter shall be less than 2 inches, and a minimum pop-up height of 4 inches. All heads shall have check valves built into the bottom of the body

Use high efficiency, multi-stream rotary nozzles for areas that range from 15 feet to 30 feet wide. Single stream rotors may be used in areas larger than 30 feet. Use nozzles for single stream rotors that provide matched precipitation rates. Radius reduction for single stream rotary heads shall be avoided as much as possible and shall not exceed 25 percent of the maximum or as indicated in manufacturer's catalog.

P. Flow Sensors

Flow sensors are recommended and encouraged though not required. Flow sensors will limit water waste and loss and minimize leaks and unscheduled flows by shutting down the system and alerting the system manager if problems occur. If flow sensors are used, ensure that the specified controller has flow sensing capabilities.

2.07 PERFORMANCE STANDARDS FOR WATER USES

Each project shall be designed to allow a maximum peak hydraulic capacity of 28 inches (17.46 gallons) of water per square foot annually for irrigated turfgrass. Rainfall is not included in this total. Water use can be calculated by plant requirements by type or hydrozones. Hydrozones shall be defined into the following levels of water requirements:

Table 2.02: Water Use by Hydrozone

Hydrozone	Plant Type	Water Budget	
		Inches/Sq Ft/Yr	Gallons/Sq Ft/Yr
High	Turf Grass	28.0	17.46
Moderate	Shrubs and Perennials	18.7	11.70
Low	Low Water Use Turf	14.0	8.73
Very Low	Xeric Shrubs and Perennials	7.00	4.36

If plant types or hydrozones are mixed, the higher usage plant material should be used for calculation purposes. Traditional or typical shrubs and perennials require 33% less water than turf or 11.7 gallons of water per sq.ft. per season. Low water use turf should use 50% (or less) of the water of irrigated turfgrass or 8.73 gallons per square foot per season. Non-irrigated turf is not expected to use any water following first year establishment unless prior approval by the District is obtained. Xeric shrubs and xeric perennials require 75% less water than irrigated turf or 4.36 gallons per square foot after establishment.

Calculation: One acre of irrigated turf (lawn) calculates out as 43,560 sq.ft. x 28" x 0.623 = 759,860 gallons of water per season.

A calculation of the irrigated areas by plant type or hydrozone and the expected annual water requirements of each and the total annual water requirement shall be provided with the design submittal.

2.08 TAP SIZING FOR LANDSCAPE IRRIGATION

Required minimum meter size based on adjusted irrigated area:

Table 2.03: Tap Size

Adjusted Irrigated Area (Sq Ft)	Meter Size
Up to 25,000	3/4"
Up to 50,000	1"
Up to 110,000	1-1/2"
Up to 200,000	2"
Up to 400,000	3"

To calculate, add the adjusted square footage of the other irrigated landscape areas to the irrigated turf square footages to arrive at a total equivalent of irrigated turf area and then determine the required meter size from Table 2.03 above. Please use the following calculations and submit a summary with the submittal.

Table 2.04: Adjusted Irrigated Area

Plant Type	Design Area	Adjusted Area
Irrigated Turf Grass	<i>sq.ft</i>	<i>sq.ft.</i>
Low Water Use Turf Grass	<i>sq.ft. x 0.5</i>	<i>sq.ft.</i>
Native and Non-Irrigated Grass	<i>sq.ft. x 0.5</i>	<i>sq.ft.</i>
Non-Turf Area: Traditional Shrubs and Perennials	<i>sq.ft. x 0.25</i>	<i>sq.ft.</i>
Non-Turf Area: Xeriscape or Xeric Shrubs and Perennials	<i>sq.ft. x 0.25</i>	<i>sq.ft.</i>
Non-Turf Area: Annual Flowers and Color Beds	<i>sq.ft. x 0.25</i>	<i>sq.ft.</i>
Tree Only Area	<i>sq.ft. x 0.25</i>	<i>sq.ft.</i>
TOTAL ADJUSTED IRRIGATED AREA =		<i>sq.ft.</i>

TAP SIZE = _____ - based on above Tap Size Table 2.03.

2.09 IRRIGATION SCHEDULE

An irrigation schedule for the highest ET demand week of the season shall be included on the plans. The irrigation schedule shall include:

- A. Station #
- B. Sprinkler Type
- C. Hydrozone
- D. Runtime
- E. Number of cycles per day
- F. Frequency of irrigation for each zone

Table 2.05 – Sample Irrigation Schedule

Station #	Hydrozone	Sprinkler Type	PR	Max Weekly ET	Total Run Time	Frequency	Soil Infiltration Rate	Cycles	Cycle Time
A1	High	Rotary Spray	0.45	1.8	240	3	0.2	3	27
A2	Low	Spray	1.00	0.9	54	3	0.2	5	4

2.10 TAP FEES

The applicant shall contact the District to determine the tap connection fees. The fees will be calculated based on the Rates, Fees, & Charges identified in the District's Rules & Regulations. The fee calculation includes but is not limited to planting area and meter size for all permanent irrigation. Table 2.06 illustrates the cost per area depending on plant type.

Table 2.06: Cost Per Irrigated Area

Plant Type	Cost Per SQ FT
Irrigated Turf Grass	\$1.52
Low Water Use Turf Grass	\$1.21
Native and Non-Irrigated Grass	\$0.33
Non-Turf Area:	\$0.55
Tree Only Area	\$0.33

For a non-potable irrigation system, irrigation taps will be charged 80% of the potable tap fee.

Temporary irrigation to establish native seeding will be allowed for one irrigation season, subject to District approval. A tap fee for the temporary irrigation will be required after one irrigation season if the Developer does not prove to the District that the temporary irrigation has been physically disconnected from the rest of the irrigation. If the tap fee is not paid, the water service will be shut off until payment is received.

2.11 PRE-CONSTRUCTION MEETING

The District and its Irrigation Consultant shall meet with the applicant that is installing the irrigation system prior to the start of the installation. The purpose of this meeting is to do a general review the project, to review the Irrigation Requirements, and to discuss the required inspections from the District. After the preconstruction meeting is held, the contractor shall, at least 48 hours prior to the start of construction, notify the District of construction schedule and start date.

2.12 CONSTRUCTION OBSERVATION

The District or its representatives may also conduct random, spot checking of the installation work in progress to check for general compliance of the equipment and workmanship to the approved irrigation design.

A hydrostatic mainline inspection shall be performed to confirm that there are no leaks in the mainline. Backfilling of the mainline is permitted, however all joints and fittings shall remain exposed for visual inspection. The mainline shall be pressurized at static pressure and isolated for a minimum of 2 hours prior to the inspection. A pressure gauge shall be installed on the isolated mainline section prior to the 2 hour test and the pressure recorded at that time. Any leaks discovered shall be repaired and the test shall be performed again until all leaks have been repaired. A 3 Business Day notice must be provided to the District in advance to schedule this inspection. Once the inspection is completed and approved, the remaining mainline may then be backfilled.

If at any time, the applicant has any questions including: system requirements, design, efficiency, allowable substitutions or changes, inspections, or the District requirements, please contact the District with any needs, questions, requests, or concerns.

2.13 FINAL INSPECTION

The applicant shall notify the District within 7 days after installation of the irrigation system to allow for scheduling of Final Inspections. The company name, contact name, phone number and email of the irrigation company will be provided to the District.

The District or its representatives must conduct a Final Inspection of the irrigation system to determine the general quality of work, meeting irrigation system and efficiency requirements, and to verify general compliance with plans and specifications. The District or its representative will inspect and review the system for general compliance to the plans as drawn and submittals and as approved including use of the specified products or products which are equivalent or greater in quality and efficiency, system pressure, controller settings, etc.

If the system or parts of it are found not to be in compliance or as approved on the submitted plans, the District can require compliance. During installation, it is the applicant must contact the District if any question, change, or significant deviation occurs or may occur which could affect water usage or system efficiency that is different from the submitted and approved plan.

The District or its representatives are not responsible for the quality of materials or workmanship, or for compliance with the District's irrigation requirements. It is not the intent of the District to be punitive to the applicant with respect to the construction observation and final inspection, but rather to have a quality, efficient irrigation system for the benefit of the District, its customers, and the community. The District reserves the right to adjust the meter calculation figures,

tap fees, withhold water service, or terminate water service if the irrigation requirements including inspections are not followed.

2.14 SYSTEM EFFICIENCY TEST

It is important that an irrigation system is properly designed and installed with the newer, more efficient components and equipment to achieve ongoing system efficiency and water savings. A representative catch cup, DU test shall be conducted to calculate the system efficiency of tested stations or zones. The greater of, either: two zones (minimum per tap) or 5% of the spray or rotary zones on a tap will be tested. Drip zones may be checked for proper operation, but will not be specifically subject to the efficiency testing. The test shall conform to Irrigation Association standards and shall be completed by an independent, Irrigation Association Certified Auditor approved by the District.

The District's minimum DU on a new system shall have a 70% or greater distribution uniformity, if the District's 70% DU Efficiency Standard is not met, the auditor should provide written recommendations to correct or increase the system's efficiency. System inefficiencies shall be corrected within 30 days and then the catch cup test will be repeated. If the system still does not meet the 70% Efficiency Standard then the District will review options to increase the efficiency. Results of the DU and System Efficiency Test(s) should be provided to the District including: the Testing Company's Name, Person Performing the testing, and their contact information. Efficiency tests cannot be performed by the installer's staff and must be performed by an independent, third party auditor.

2.15 SYSTEM MAINTENANCE, CONTROLLER SCHEDULING, AND SYSTEM AUDITING

A. Maintenance Requirements

The applicant is expected to provide ongoing management and maintenance of the irrigation system for the efficient ongoing operation.

System checks should be done on the entire system a minimum of monthly, but more preferably every 1-2 weeks to verify that the system is operating efficiently and properly and to minimize water lost due to malfunctions that are left unrepaired for extended periods of time. Heads and lines will be observed while the system is operating and checked for proper functioning, coverage, excessive overspray, and any leaks. Adjustments and repairs are to be made as needed and on a timely basis to keep the system operating efficiently.

When system repairs are made, especially heads and nozzles, they shall be replaced with identical components/parts with matched precipitation and identical performance characteristics. Random mixing of heads, nozzles, and other components when system repairs are made over time is not acceptable and will reduce system performance and lead to decreased efficiency.

B. System Operation and Controller Management

Systems shall be properly programmed and set up initially and then operated to irrigate in an efficient, water conserving manner on an ongoing basis. Weather-based, ET Controllers shall be properly programmed and any required subscriptions shall be paid up and kept current. Rain, Soil, or other sensors or weather stations shall also be checked for proper operation a minimum of two times per season.

Controllers shall be checked for proper operation and adjusted as needed. Even "Smart" Controllers should be checked regularly. Scheduled watering days shall be based on the District's current and allowed watering days and times. Controller setup and functioning shall be checked a minimum of monthly during the irrigation season to make sure the controllers are setup and operating properly. Any controller alarms or alerts shall be corrected and addressed when or as they occur.

C. Landscape Irrigation Audit Schedule

The District recommends an irrigation audit be performed every 5 years by an independent, Irrigation Association certified auditor approved by the District. A copy of the audit shall be provided to the Property Manager and the District when completed along with any planned or completed repairs or adjustments to be made or other comments as a result of the audit.


A catch cup, DU test should be provided with the audit to calculate system efficiency of the tested stations or zones to ensure the system efficiency is adequately maintained. The DU test should be conducted after all repairs have been made to the system.

The intent of this audit is to verify that the system at the subject's property is being operated in an effective and efficient manner and to make note of any efficiency needs or issues with the system operation and functioning. If efficiency issues or deficiencies are found, these repairs or adjustments should be promptly corrected.


APPENDIX A

WATER SYSTEM CONSTRUCTION DETAILS

ECCV-1W Standard Bedding For Water Lines



PLAN



ELEVATION A-A

MATERIALS:

- ⑧ 12" COPPERSETTER / METER YOKE WITH BYPASS:
 - FORD "CUSTOM SETTER" METER UNIT
 - 1½" MODEL NO. VBH76-12-11-66-NL, METER SPACING = 13"
 - 2" MODEL NO. VBH77-12-11-77-NL METER SPACING = 17"
 - YOKE SHALL HAVE LOCKING ANGLE BALL METER ON INLET & ANGLE CHECK VALVE ON OUTLET
- ⑨ BALL VALVE WITH HANDLE

NOTES:

1. WATER METER FURNISHED BY DISTRICT. INSTALLATION TO BE DONE BY CONTRACTOR
2. SERVICE LINE MUST HAVE MIN. 4.5 FEET OF COVER.
3. DISTRICT PERSONNEL SHALL INSPECT THE SERVICE LINE FROM THE MAIN TO THE METER PRIOR TO BACKFILLING.
4. DISTRICT PERSONNEL SHALL INSPECT THE SERVICE LINE FROM THE METER TO THE BUILDING PRIOR TO BACKFILLING.
5. CONCRETE SHALL NOT BE LAID IN FLOOR OF METER MANHOLE.
6. MANHOLE BASE BEAMS REQUIRED FOR INSTALLATIONS IN DRIVEWAYS OR PARKING AREAS.
7. FIELD SOLDERED JOINTS OR PLASTIC PIPE ARE NOT ALLOWED IN METER MANHOLE.
8. DISTRICT PERSONNEL SHALL INSPECT THE CORPORATION STOP AND INSULATING COUPLING PRIOR TO BACKFILLING.
9. NO TAPS OR CONNECTIONS ALLOWED WITHIN 5 FEET OF THE METER.
10. ALL BOLTS SHALL BE STAINLESS STEEL.
11. NO BACKFLOW PREVENTION ASSEMBLY ALLOWED IN METER PIT
12. NO FLARE FITTINGS
13. BYPASS NOT PERMITTED FOR IRRIGATION ONLY METER SETTINGS.

MATERIALS:

- ① WATER SERVICE LINE - COPPER TUBING (TYPE K) 4.5 FEET MIN. COVER
- ② CURB STOP VALVE WITH 2" SQUARE NUT AND ARCH-PATTERN BUFFALO STYLE VALVE BOX
- ③ WATER METER
- ④ RING AND COVER - 24" DEETER #1258 OR CASTINGS INC. C.I.24 RECESSED OR EQUAL, "WATER" CAST INTO COVER. LIDS SHOULD HAVE 2" HOLE IN THE CENTER. ALL COVERS SHOULD BE H-20 TRAFFIC LOADING RATED.
- ⑤ PRECAST 60" ID MANHOLE - ASTM C-478 WITH MANHOLE STEPS, OFFSET FLAT TOP, AND CONCRETE ADJUSTMENT RINGS.
- ⑥ COPPER TUBE COMPRESSION UNION
- ⑦ TRACER WIRE



1-1/2" AND 2" IRRIGATION ONLY METER IN MANHOLE WITHOUT BYPASS

DRAWING NO.: ECCV-48W

DATE: 2024

REV. DATE: 2026

KJ Kennedy Jenks

215 Union Boulevard, Suite 500
Lakewood, CO 80228 P: 303.985.3636